


EROSION CONTROL PLAN

SCALE: 1" = 60'

EROSION CONTROL KEYNOTES

1. INSTALL TEMPORARY TURTLE EXCLUSION GATE
2. INSTALL SPECIES EXCLUSION FENCE (3,200 LF)
3. INSTALL EROSION CONTROL BLANKET (85,100 SF)
4. INSTALL COMPOST FILTER SOCK (2300 LF)
5. CONCRETE WASHOUT FACILITY
6. INSTALL"WING" OF SPECIES EXCLUSION FENCE

GENERAL NOTES

1. REFERENCE DRAWING DVB-C1-101 FOR DETAILED GRADING PLAN.
2. PROPOSED EROSION CONTROL AND SEDIMENT CONTROL MEASURES ARE SHOWN ON THIS DRAWING. SUBSTATION EQUIPMENT AND LAYOUT ARE SHOWN FOR REFERENCE ONLY.
3. REFERENCE STORMWATER POLLUTION AND PREVENTION PLAN (SWPPP) FOR CONSTRUCTION SEQUENCE, EROSION CONTROL MEASURE BEST PRACTICES, AND REPORTING REQUIREMENTS AND FREQUENCY.
4. THE EROSION AND SEDIMENT CONTROL MEASURES SHOWN IN THIS DRAWING ARE THE MINIMUM REQUIRED. SUBCONTRACTOR SHALL INSTALL AND MAINTAIN ADDITIONAL MEASURES AS REQUIRED ACCORDING TO SITE CONDITIONS THROUGHOUT CONSTRUCTION TO BE CONSISTENT WITH THE NEW YORK STORMWATER MANUAL.
5. THE SUBCONTRACTOR SHALL INSTALL AND MAINTAIN ALL EROSION CONTROL MEASURES IN THEIR INTENDED WORKING ORDER AND CONDITION AND BE IN STRICT CONFORMANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL (THE "BLUE BOOK"). THE SUBCONTRACTOR SHALL SUPPLY AND MAINTAIN ONSITE DURING THE DURATION OF CONSTRUCTION THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR SOIL EROSION AND SEDIMENT CONTROL (THE "BLUE BOOK") AND THE THE PROJECT SWPPP.
6. A SUPPLY OF EROSION CONTROL MATERIAL AS OUTLINED IN THIS PLAN AND THE EROSION CONTROL DETAILS WILL BE KEPT ONSITE AT ALL TIMES FOR MAINTENANCE, REPAIRS, AND ADDITIONAL MEASURES AS REQUIRED.
7. A CONSTRUCTION ENTRANCE SHALL BE INSTALLED AT THE BEGINNING OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF CONSTRUCTION. ALL SEDIMENT TRACKED ONTO PUBLIC ROADWAYS SHALL BE REMOVED IMMEDIATELY.
8. ALL EARTH STOCKPILES SHALL BE STABILIZED IN ACCORDANCE TO DETAILS SHOWN IN THESE PLANS. ANY PILE TO REMAIN IN PLACE FOR MORE THAN 2 MONTHS SHALL BE TEMPORARILY SEEDED. STOCKPILES TO CONFORM TO SOIL STOCKPILE PRACTICES OUTLINED IN BLUE BOOK.
9. WATER SHALL BE USED FOR DUST CONTROL IN AREAS AS APPROPRIATE.
10. ALL EROSION AND SEDIMENT CONTROL MEASURES SHALL BE PLACED BEFORE COMMENCEMENT OF CONSTRUCTION AND SHALL REMAIN IN PLACE AND MAINTAINED UNTIL SITE IS PERMANENTLY STABILIZED.
11. MAXIMUM SLOPES SHALL BE 3:1 UNLESS OTHERWISE NOTED.
12. EROSION CONTROL BLANKETS SHALL BE USED FOR ALL DISTURBED SLOPES 3:1 OR STEEPER. ALL SLOPES SHALL BE SEEDED. DRIVEWAY OR ROAD SHOULDER AND BANKS SHALL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING.
13. THE SUBCONTRACTOR SHALL MAINTAIN ACCESS TO ALL AFFECTED AREAS THROUGH THE DURATION OF CONSTRUCTION.
14. TEMPORARY AND PERMANENT SEEDING PRACTICES SHALL BE IN ACCORDANCE WITH THE BLUE BOOK.
15. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR REUSE WHERE REQUIRED. ALL TOPSOIL STOCKPILES SHALL BE SEEDED, MULCHED OR HAYED, AND ENCLOSED BY A SILT FENCE OR STRAW WATTLE.
16. ALL INLET AND OUTLET PROTECTION MEASURES SHALL BE PLACED AND MAINTAINED AS SHOWN IN THIS PLAN AND ON DETAILS.
17. CRUSHED ROCK PAVEMENT AND BASE ROCK SHALL BE INSTALLED OVER INDICATED AREAS IMMEDIATELY AFTER FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES HAVE BENE INSTALLED.
18. PLACE TOPSOIL, FINAL SEED, AND MULCH IN ACCORDANCE WITH THE BLUE BOOK SEEDING REGULATIONS IN AREAS NOT RECEIVING CRUSHED ROCK PAVEMENT. REMOVE EROSION AND SEDIMENT CONTROL MEASURES ONLY AFTER SITE HAS BEEN STABILIZED AND APPROVED BY OWNER AND APPLICABLE REGULATORY AGENCIES.
19. AN AREA SHALL BE CONSIDERED TO HAVE ACHIEVED FINAL STABILIZATION WHEN IT HAS A MINIMUM OF 80% UNIFORM PERENNIAL VEGETATIVE COVER OR OTHER PERMANENT NON-VEGETATIVE COVER WITH A DENSITY SUFFICIENT TO RESIST ACCELERATED SURFACE EROSION AND SUBSURFACE CHARACTERISTICS SUFFICIENT TO RESIST SLIDING OR OTHER MOVEMENTS.

LEGEND

- PROJECT SITE
- PROPERTY LINE
- 470 EXISTING CONTOURS
- 470 FINISHED GRADE MAJOR CONTOUR
- 469 FINISHED GRADE MINOR CONTOUR
- 484.5 PROPOSED INTERMEDIATE CONTOURS
- PROPOSED FENCE
- LOD LIMIT OF DISTURBANCE
- FLOWLINE
- FLOW ARROW
- PROPOSED PRESERVATION LINE AND PRESERVED WOODED AREA
- PROPOSED LANDSCAPE AND GRASS AREAS
- CULVERT
- SUBSTATION AREA SECTION
- ACCESS ROAD SECTION
- RIPRAP
- EXISTING USACE WETLANDS
- EXISTING NYSDEC WETLANDS
- 100-FT WETLAND BUFFER
- TRANSMISSION POLE
- CONSERVATION ZONE 2

EROSION CONTROL LEGEND

- SENSITIVE SPECIES EXCLUSION FENCE
- COMPOST FILTER SOCK
- CONCRETE WASHOUT
- EROSION CONTROL BLANKET
- TEMPORARY EXCLUSION GATE

0 30 60 120 180 FEET

1" = 60'

STATE OF NEW YORK WILLIAM H. ROMINES, JR LICENSED PROFESSIONAL ENGINEER 104002

WILLIAM H. ROMINES, JR PE # 104002

PROJECT LOCATION:
2238 ROUTE 22
DOVER, NY 12594

DVB-C1-104.DWG

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR

REFERENCE DRAWINGS

DSGN	BHR	06-16-21
DRN	BLW	07-02-21
CKD	BHR	08-12-22

SCALE: AS NOTED

FOR 24x36 DWG ONLY

POWER ENGINEERS

NY TRANSCO


DOVER STATION

EROSION CONTROL PLAN

JOB NUMBER 169978

REV C

DRAWING NUMBER DVB-C1-104




SUBSTATION SECTION
INFILTRATION RATE < 0.5 IN/HR
(PERMEABLE)

NTS


NOTES

1. ALL FILL USED FOR SIDE SLOPES SHALL BE ONSITE MATERIAL FROM AREA CUT TO CREATE THE SUBSTATION OR SHALL BE OFFSITE FILL COMPACTED TO HAVE AN INFILTRATION RATE LESS THAN THE SUBSTATION SUBGRADE.
2. UNDERDRAIN SIZE AND LAYOUT WILL VARY DEPENDING ON THE SIZE OF THE SUBSTATION.
3. UNDERDRAINS SHALL BE SIZED TO MEET CHANNEL PROTECTION VOLUME (Cpv), OVER BANK FLOOD CONTROL (Qp) AND EXTREME FLOOD CONTROL (Qf) DESIGN CRITERIA.
4. THIS SECTION SHALL BE APPLICABLE TO MEET THE STORMWATER MANAGEMENT REQUIREMENTS OF NEW DEVELOPMENT AND REDEVELOPMENT PROJECTS, PER THE 2015 NYS STORMWATER MANAGEMENT DESIGN MANUAL, FOR SITES WITH INFILTRATION RATES LESS THAN 0.5 INCHES PER HOUR.



TYPICAL ACCESS ROAD SECTION
(IMPERMEABLE)

NTS




TYPICAL RIPRAP DETAIL

NTS

NOTES

1. RIPRAP APRONS AT PIPE OUTLETS TO BE SIZED IN ACCORDANCE WITH NYSDEC STANDARDS.




PLASTIC SHEETING

STOCKPILE OR SURCHARGE SHEETING DETAIL


NTS

NOTES


1. MINIMUM 12" OVERLAP OF ALL SEAMS REQUIRED.
2. BARRIER REQUIRED AT TOE OF STOCK PILE.
3. COVERING MAINTAINED TIGHTLY IN PLACE BY USING SANDBAGS OR TIRES ON ROPES WITH A MAXIMUM 18' GRID SPACING IN ALL DIRECTIONS.
4. BARRIERS SHALL BE CONSTRUCTED WITH SEDIMENT FENCES, MULCH BERMS, CLIPPINGS, STRAW WATTLES, OR OTHER APPROVED MATERIALS.



HINGE BOLT DETAIL




HINGES



SLIDE LOCK DETAIL

NOTES

1. CUT FROM 4" X 6" X½" RECT TUBING



34' ROW GATE DOUBLE LEAF
TUBULAR WITH BURIED CROSS BEAM

NTS

NOTES

1. ENTIRE GATE ASSEMBLY SHALL BE PRIMED & TOP COATED FOREST GREEN AFTER FABRICATION.

STATE OF NEW YORK · WILLIAM H. ROMINES, JR · 104002 · LICENSED PROFESSIONAL ENGINEER

WILLIAM H. ROMINES, JR PE # 104002

PROJECT LOCATION
2238 ROUTE 22
DOVER, NY 12594

DVB-C1-112.DWG

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR

REFERENCE DRAWINGS

DSGN	BHR	06-16-21
DRN	BRG	06-16-21
CKD	BHR	08-12-22

SCALE: AS NOTED

FOR 24x36 DWG ONLY

POWER ENGINEERS

NY TRANSCO


DOVER STATION

SITE DETAILS

JOB NUMBER 169978

REV C

DRAWING NUMBER DVB-C1-112




PLAN

PIT SIZING CHART		
(APPROX.) VOLUME OF SPOILS	(MIN) WIDTH (W)	DEPTH (D)
5 CY OR LESS	3'-0"	12"
5 TO 20 CY	10'-0"	12"
* 20 CY OR MORE	15'-0"	18"


* UTILIZE FOR SITE

NOTES

1. ULTIMATE WASHOUT SIZE DETERMINED BY AMOUNT OF CONCRETE REQUIRED FOR PROJECT AREA AND/OR POUR LOCATION.
2. THE CONCRETE WASHOUT SIGN SHALL BE INSTALLED WITHIN 20' OF THE TEMPORARY CONCRETE WASHOUT.




SECTION A
NTS



SECTION B
NTS

TYPICAL TEMPORARY CONCRETE WASHOUT FACILITY DETAIL

NTS




TYPICAL FIBER ROLL DETAIL

NTS

NOTES

1. OVERLAP FIBER ROLLS (APPROX) 10'-0" RATHER THAN ABUTING AT CONNECTIONS.
2. INSTALL FIBER ROLL ALONG A LEVEL CONTOUR.
3. INSTALL A FIBER ROLL NEAR SLOPE, WHERE IT TRANSITION INTO A STEEPER SLOPE.
4. VERTICAL SPACING BETWEEN FIBER ROLLS ARE MEASURED ALONG THE FACE OF THE SLOPE.




SECTION C
NTS

NOTES


1. INSTALL FIBER ROLL 2-4 INCHES ON DEPTH, SUCH THAT RUNOFF WILL NOT BE ALLOWED UNDER OR AROUND. TRENCH SHALL BE EXCAVATED ALONG THE CONTOUR.
2. WOODEN STAKE SHALL BE A MINIMUM 2'-0".
3. INSTALL FIBER ROLLS INSIDE FENCELINE WHERE APPLICABLE, MINIMUM 1FT SPACED FROM FENCE.

STRAW BALE BARRIERS

1. BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE ON THE CONTOUR, WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER.
2. ALL BALES SHALL BE EITHER WIRE-BOUND OR STRING-TIED. STRAW BALES SHALL BE INSTALLED SO THAT BINDINGS ARE ORIENTED AROUND THE SIDES RATHER THAN ALONG THE TOPS AND BOTTOMS OF THE BALES IN ORDER TO PREVENT DETERIORATION OF THE BINDINGS.
3. THE BARRIER SHALL BE ENTRENCHED AND BACK FILLED. A TRENCH SHALL BE EXCAVATED THE WIDTH OF A BALE AND THE LENGTH OF THE PROPOSED BARRIER TO A MINIMUM DEPTH OF 4 INCHES. THE TRENCH MUST BE DEEP ENOUGH TO REMOVE ALL GRASS AND OTHER MATERIAL WHICH MIGHT ALLOW UNDERFLOW. AFTER THE BALES ARE STAKED AND CHINKED (FILLED BY WEDGING), THE EXCAVATED SOIL SHALL BE BACK FILLED AGAINST THE BARRIER. BACK FILL SOIL SHALL CONFORM TO THE GROUND LEVEL ON THE DOWNHILL SIDE AND SHALL BE BUILT UP TO 4 INCHES AGAINST THE UPHILL SIDE OF THE BARRIER.
4. EACH BALE SHALL BE SECURELY ANCHORED BY AT LEAST 2 STAKES OR REBARS DRIVEN THROUGH THE BALE. THE FIRST STAKE IN EACH BALE SHALL BE DRIVEN TOWARD THE PREVIOUSLY LAID BALE TO FORCE THE BALES TOGETHER. STAKES OR REBARS SHALL BE DRIVEN DEEP ENOUGH INTO THE GROUND TO SECURELY ANCHOR THE BALES. STAKES SHOULD NOT EXTEND ABOVE THE BALES BUT INSTEAD SHOULD BE DRIVEN IN FLUSH WITH THE TOP OF THE BALE FOR SAFETY REASONS.
5. THE GAPS BETWEEN THE BALES SHALL BE CHINKED (FILLED BY WEDGING) WITH STRAW TO PREVENT WATER FROM ESCAPING BETWEEN THE BALES. LOOSE STRAW SCATTERED OVER THE AREA IMMEDIATELY UPHILL FROM A STRAW BALE BARRIER TENDS TO INCREASE BARRIER EFFICIENCY. WEDGING MUST BE DONE CAREFULLY IN ORDER NOT TO SEPARATE THE BALES.
6. INSPECTION SHALL BE FREQUENT AND REPAIR OR REPLACEMENT SHALL BE MADE PROMPTLY AS NEEDED.
7. STRAW BALE BARRIERS SHALL BE REMOVED WHEN THEY HAVE SERVED THEIR USEFULNESS, BUT NOT BEFORE THE UP-SLOPE AREAS HAVE BEEN PERMANENTLY STABILIZED. BALES SHALL BE PLACED IN A SINGLE ROW, LENGTHWISE, ORIENTED PERPENDICULAR TO THE CONTOUR, WITH ENDS OF ADJACENT BALES TIGHTLY ABUTTING ONE ANOTHER.
8. THE REMAINING STEPS FOR INSTALLING A STRAW BALE BARRIER FOR SHEET FLOW APPLICATIONS APPLY.
9. THE BARRIER SHALL BE EXTENDED TO SUCH A LENGTH THAT THE BOTTOMS OF THE END BALES ARE HIGHER IN ELEVATION THAN THE TOP OF THE LOWEST MIDDLE BALE TO ASSURE THAT SEDIMENT-LADEN RUNOFF WILL FLOW EITHER THROUGH OR OVER THE BARRIER BUT NOT AROUND IT.



EMBEDDING DETAIL



STRAW BALE SILT FENCE DETAIL

NTS

STATE OF NEW YORK
WILLIAM H. ROMINES, JR
104002
LICENSED PROFESSIONAL ENGINEER

WILLIAM H. ROMINES, JR PE # 104002

PROJECT LOCATION:
2238 ROUTE 22
DOVER, NY 12594

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD	REFERENCE DRAWINGS
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR	
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR	
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR	


DSGN	BHR	06-16-21
DRN	BRG	06-16-21
CKD	BHR	08-12-22
SCALE:	AS NOTED	
FOR 24x36 DWG ONLY		

POWER ENGINEERS


NY TRANSCO
DOVER STATION
SITE DETAILS

JOB NUMBER 169978
REV C
DRAWING NUMBER DVB-C1-113

DVB-C1-113.DWG




PLAN




BOTTOM OF SLOPE TERMINATION DETAIL

NTS




END ROLL OVERLAP DETAIL

NTS




ELEVATION



SLOPE TRENCHING DETAIL

NTS




SIDE SEAM OVERLAP DETAIL

NTS

NOTES

STAPLE PATTERNS ARE DEPENDENT ON SITE CONDITIONS, INSTALL PER MANUFACTURER'S RECOMMENDATIONS.


"SEDIMENT CONTROL FABRIC"
FABRIC SHALL BE USED FOR INSTALLATIONS OF SHORT DURATION. THE FABRIC IS CUT ON SITE TO THE DESIRED WIDTH, UNROLLED ALONG THE LENGTH OF THE BARRIER AND DRAPED OVER THE BARRIER. THE FABRIC TOE IS SECURED WITH ROCKS OR DIRT AND THE FABRIC COVERING THE BARRIER IS SECURED TO THE BARRIER WITH TWINE, STAPLES, OR SIMILAR DEVICES. AFTER THE CONSTRUCTION AREA IS STABILIZED AND EROSION ACTIVITY CURTAILED, THE SEDIMENT BARRIERS ARE REMOVED AND THE CONTAINED SEDIMENT IS LEVELED, SEEDED, AND MULCHED. SPECIAL PROTECTION OF THE SEED BED MAY BE NECESSARY IF THE LAYERS ARE OVER A FOOT THICK.



SECTION

SILT FENCE DETAIL

NTS



EROSION CONTROL BLANKET

NTS

NOTES

1. SLOPE SHALL BE FREE OF ROCKS, CLODS, STICKS, ETC AND GRADED UNIFORMLY TO PROVIDE MAT HAS GOOD SOIL CONTACT.
2. SIMILAR MATTING TO BE USED IN SWALES.
3. INSTALL PER MANUFACTURER'S RECOMMENDATIONS.
4. BLANKETED AREAS TO BE INSPECTED WEEKLY AND AFTER EACH RAINFALL EVENT UNTIL PERENNIAL VEGETATION IS ESTABLISHED TO A MINIMUM UNIFORM 70% COVERAGE THROUGHOUT THE BLANKETED AREA. DAMAGED OR DISPLACED BLANKETS TO BE RESTORED OR REPLACED WITHIN 4 CALENDAR DAYS.

STATE OF NEW YORK
WILLIAM H. ROMINES, JR
LICENSED PROFESSIONAL ENGINEER
104002

WILLIAM H. ROMINES, JR PE # 104002

PROJECT LOCATION:
2238 ROUTE 22
DOVER, NY 12594

DVB-C1-114.DWG

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR

REFERENCE DRAWINGS

DSGN	BHR	07-27-21
DRN	BRG	07-27-21
CKD	BHR	08-12-22

SCALE: AS NOTED

FOR 24x36 DWG ONLY

POWER ENGINEERS

NY TRANSCO

DOVER STATION

SITE DETAILS


JOB NUMBER 169978

REV C

DRAWING NUMBER DVB-C1-114


BOG TURTLE AND TIMBER RATTLESNAKE ENCOUNTERED PROCEDURES

- A BOG TURTLE AND TIMBER RATTLESNAKE EDUCATION AND ENCOUNTER PLAN HAS BEEN PREPARED AND WILL BE GIVEN TO GIVEN TO CONSTRUCTION WORKERS AND FUTURE PROPERTY MAINTENANCE STAFF TO NOTIFY THEM OF THE POTENTIAL PRESENCE OF BOG TURTLES AND TIMBER RATTLESNAKES ONSITE, PROCEDURES TO USE SHOULD THEY ENCOUNTER A BOG TURTLE OR TIMBER RATTLESNAKE, AND HOW THE PROPERTY WILL BE MAINTAINED IN THE FUTURE TO AVOID POTENTIAL NEGATIVE IMPACTS TO THE SPECIES
- CONSTRUCTION PERSONNEL WILL RECEIVE TRAINING FROM A KNOWLEDGEABLE BIOLOGIST REGARDING THE SPECIES OF CONCERN AND PROPER ENCOUNTER PROCEDURES. ALL PERSONNEL WILL SIGN A LOG CERTIFYING THAT THEY HAVE RECEIVED THIS TRAINING. A LOG DOCUMENTING THE DAILY BARRIER INSPECTIONS WILL BE MAINTAINED ON SITE. SAGGING OR BULGING OF FENCE THAT MIGHT ALLOW TURTLES TO CLIMB THE FENCE MUST BE REPAIRED BEFORE WORK CAN BEGIN. IF ANY DEFICIENCIES ARE ENCOUNTERED THAT MAY HAVE ALLOWED TURTLES TO ENTER, THE AREA WITHIN THE BARRIER WILL BE INSPECTED FOR TURTLES BY THE BOG TURTLE MONITOR BEFORE WORK BEGINS.
- IF A TIMBER RATTLESNAKE OR BOG TURTLE IS FOUND WITHIN THE BARRIER, ALL WORK WILL STOP AND WILL NOT RESUME UNTIL THE LICENSED MONITOR HAS MOVED THE ANIMAL TO SAFETY, INSPECTED THE BARRIER FOR DEFICIENCIES THAT ALLOWED THE ANIMAL TO ENTER, SUPERVISED ANY NECESSARY REPAIR OF THE BARRIER, AND INSPECTED THE AREA INSIDE THE BARRIER FOR ANY ADDITIONAL ANIMALS. IF YOU SEE A BOG TURTLE OR TIMBER RATTLESNAKE ON THIS SITE:
  - STOP WORK IN THE AREA IN WHICH THE TURTLE/SNAKE IS FOUND. NO MACHINERY OR VEHICLES SHOULD BE OPERATING IN THE AREA.
  - DO NOT TOUCH OR TRY TO MOVE OR HARASS THE TURTLE/SNAKE. TURTLES CAN BITE AND SCRATCH WITH SHARP CLAWS. SNAKE CAN BITE AND SOME, INCLUDING TIMBER RATTLESNAKES ARE VENOMOUS. ONLY TRAINED AND EXPERIENCED INDIVIDUALS SHOULD HANDLE TURTLES/SNAKES. BY ALLOWING THE TURTLE/SNAKE TO CONTINUE ON ITS WAY THEY CAN SOMETIMES REMOVE THEMSELVES FROM THE CONSTRUCTION AREA.
  - ASSIGN AN ONSITE REPRESENTATIVE TO KEEP AN EYE ON THE TURTLE/SNAKE AND MONITOR ITS MOVEMENTS FROM A SAFE DISTANCE (MINIMUM OF 10 FEET FOR TIMBER RATTLESNAKES). ALERT ALL PERSONNEL ONSITE OF THE PRESENCE OF THE SNAKE/TURTLE.
  - IF THE TURTLE IS IDENTIFIED AS A BOG TURTLE, ONLY A NYSDEC LICENSED AND USFWS QUALIFIED TURTLE MONITOR (BOG TURTLE MONITOR) AND/OR DESIGNATED AGENT CAN REMOVE THE SPECIES FROM THE SITE. THIS IS DUE TO THE FEDERAL/STATE REGULATIONS ON BOG TURTLES WHICH ONLY ALLOW QUALIFIED INDIVIDUALS TO HANDLE THE SPECIES.
  - IF THE SNAKE IS IDENTIFIED AS A TIMBER RATTLESNAKE, ONLY A NYSDEC LICENSED PROFESSIONAL (TIMBER RATTLESNAKE PROFESSIONAL) AND/OR DESIGNATED AGENT CAN REMOVE THE SPECIES FROM THE SITE. THIS IS DUE TO THE STATE REGULATIONS ON TIMBER RATTLESNAKES, WHICH ONLY ALLOWS LICENSED INDIVIDUALS TO HANDLE THE SPECIES.
  -REPORT THE TURTLE/SNAKE SIGHTING TO THE ENVIRONMENTAL COMPLIANCE MANAGER AND NOTIFY THE BOG TURTLE MONITOR\TIMBER RATTLESNAKE PROFESSIONAL.




TEMPORARY TURTLE EXCLUSION GATE

NTS



SPECIES EXCLUSION FENCE DETAIL

NTS



"WING" DETAIL-SPECIES EXCLUSION FENCE

NTS

NOTES

1. WINGS WILL BE IMPLEMENTED IN CONSULTATION WITH BOG TURTLE MONITOR.
2. WINGS SHOULD NOT BE CONSTRUCTED WITH TIGHT ANGLES THAT TURTLES MAY BECOME TRAPPED IN.
3. WHEN APPROACHING ROADS, THE OUTER FENCE OF THE DOUBLE ROW OF SILT FENCE WILL CURL BACK APPROXIMATELY 6 FEET IN A HORSESHOE SHAPE TO DIVERT TURTLES FROM THE ROAD. ADDITIONALLY, THE OPEN SPACE NEAR THE ENDS OF THE DOUBLE ROWS OF SILT FENCE SHALL BE CLOSED OFF WITH SILT FENCING.
4. WINGS TO BE CURVED BACK AT MINIMUM DISTANCE OF 6 FT.

NOTES

- A DOUBLE ROW OF SILT FENCING (TEMPORARY BOG TURTLE EXCLUSION BARRIER) WILL BE INSTALLED ALONG THE ENTIRE LOD BOUNDARY, IF POSSIBLE, BETWEEN OCTOBER 1 AND MARCH 31, WHEN BOG TURTLES ARE IN HIBERNATION. IF INSTALLATION OCCURS DURING THE ACTIVE SEASON (BETWEEN APRIL 1 AND SEPTEMBER 31), THEN A MONITORING BIOLOGIST, PERMITTED BY THE NYSDEC TO HANDLE BOG TURTLES, WILL BE ON SITE TO MAKE SURE THERE ARE NO BOG TURTLES IN THE WORK AREA.
- THE EXCLUSION FENCE WILL BE CONSTRUCTED IN ACCORDANCE WITH THE FOLLOWING DESIGN:
  - MADE OF STANDARD SILT FENCE OR MATERIALS APPROVED BY NYSDEC;
  - FENCING WILL BE IN TWO PARALLEL ROWS ADEQUATELY SPACED APART FROM EACH OTHER (AT LEAST 1' MINIMUM, 2' DESIRED);
  - A MINIMUM OF 30" TALL (ABOVE GROUND);
  - ANCHORED INTO THE GROUND WITH REINFORCEMENT BARS PLACED ON THE "DISTURBANCE SIDE" OF THE BARRIER AND SPACED BETWEEN 6-8 FEET APART;
  - SECURED AT THE BASE (BARRIER/GROUND INTERFACE) WITH AT LEAST 6" OF FENCE MATERIAL COVERED WITH SOIL BACKFILL;
  - ENSURE SOIL IS LEVEL WITH GRADE AND PRESSED AGAINST THE INSIDE AND OUTSIDE OF THE SILT FENCES, SO THERE IS NO POTENTIAL FOR TURTLES TO APPROACH THE FENCE AND FALL INTO A TRENCH ON EITHER SIDE OF THE FENCE; AND
  - ANY DISTURBED SOIL REMAINING ON THE OUTSIDE OF INSTALLED SILT FENCE (POST INSTALLATION) MUST BE STABILIZED IMMEDIATELY.
- THE EXCLUSION FENCE WILL BE EXAMINED EACH DAY BY CONSTRUCTION WORKERS UNTIL CONSTRUCTION ACTIVITIES ARE COMPLETE. ANY BREACHES IN FENCE THE MUST WILL BE REPAIRED IMMEDIATELY AND WORK WILL NOT BEGIN UNTIL THEY ARE REPAIRED;
- AN EDUCATION AND ENCOUNTER PLAN PAMPHLET WILL BE GIVEN TO CONSTRUCTION WORKERS AND FUTURE PROPERTY MAINTENANCE STAFF TO NOTIFY THEM OF THE POTENTIAL PRESENCE OF BOG TURTLES ONSITE, PROCEDURES TO USE SHOULD THEY ENCOUNTER A BOG TURTLE, AND HOW THE PROPERTY WILL BE MAINTAINED IN THE FUTURE TO AVOID POTENTIAL NEGATIVE IMPACTS TO THE SPECIES;
- IF A BOG TURTLE IS FOUND WITHIN THE WORK AREA, THE MONITORING BIOLOGIST WILL BE NOTIFIED TO SAFELY MOVE THE BOG TURTLE OUT

WILLIAM H. ROMINES, JR PE # 104002

PROJECT LOCATION
2238 ROUTE 22
DOVER, NY 12594

DVB-C1-115.DWG

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR

REFERENCE DRAWINGS

DSGN	APG	02-15-22
DRN	BRG	02-15-22
CKD	BHR	08-12-22

SCALE: AS NOTED

FOR 24x36 DWG ONLY

POWER ENGINEERS

NY TRANSCO

DOVER STATION


SPECIES AVOIDANCE AND CONSERVATION DETAILS

JOB NUMBER 169978

REV 0

DRAWING NUMBER DVB-C1-115

PLAN NORTH



NOTES

1. MATURE TREE HEIGHTS SECTION: NORWAY SPRUCE = 20-FT, WICHITA BLUE JUNIPER = 14-FT.
2. LANDSCAPING PLANT SELECTION MAY BE LIMITED TO AVAILABLE SPECIES AT THE TIME OF CONSTRUCTION. SPECIES WILL BE SELECTED BASED UPON CAPABILITY TO MAXIMIZE SITE SCREENING.

LANDSCAPING PLAN

SCALE: 1" = 60'

PLANT LANDSCAPING SCHEDULE

DECIDUOUS TREES	QTY	BOTANICAL NAME	COMMON NAME	SIZE	CALIPER	HEIGHT/WIDTH (AT MATURITY)
	11	Celtis Occidentalis	Common Hackberry	B & B	2" Cal.	50' x 30'

EVERGREEN TREES	QTY	BOTANICAL NAME	COMMON NAME	ROOT	HEIGHT	HEIGHT/WIDTH (AT MATURITY)
	10	Picea pungens	Fat Albert Spruce	B & B	16 @ 13' Ht, 6 @ 6' Ht	15` x 10`
	109	Juniperus scopulorum	Wichita Blue Juniper	B & B	80 @ 14' Ht, 48 @ 6' Ht	18' x 6`
	45	Picea glauca	White Spruce	B & B	6 @ 14' Ht, 35 @ 6' Ht	50` x 20`
	26	Pinus strobus	Eastern White Pine	B & B	6`-8` Ht	50` x 20`
	40	Picea abies	Norway Spruce	B & B	24 @ 20' Ht, 22 @ 6'-8' Ht	50` x 30`

DECIDUOUS SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	HEIGHT/WIDTH
	15	Ilex glabra 'Compacta'	Compact Inkberry	5 gal	3' x 3'

EVERGREEN SHRUBS	QTY	BOTANICAL NAME	COMMON NAME	SIZE	HEIGHT/WIDTH
	8	Pinus mugo 'Compacta'	Compact Mugo Pine	5 gal	5` X 5'

LEGEND

- PROJECT SITE
- PROPERTY LINE
- 470 EXISTING CONTOURS
- 470 FINISHED GRADE MAJOR CONTOUR
- 469 FINISHED GRADE MINOR CONTOUR
- 484.5 PROPOSED INTERMEDIATE CONTOURS
- x PROPOSED FENCE
- XX PRESERVATION FENCE
- LOD LIMIT OF DISTURBANCE
- FLOWLINE
- FLOW ARROW
- PROPOSED PRESERVATION LINE AND PRESERVED WOODED AREA
- PROPOSED LANDSCAPE AND GRASS AREAS
- CULVERT
- SUBSTATION AREA SECTION
- ACCESS ROAD SECTION
- RIPRAP
- EXISTING USACE WETLANDS
- EXISTING NYSDEC WETLANDS
- 100-FT WETLAND BUFFER
- TRANSMISSION POLE
- CONSERVATION ZONE 2

0 30 60 120 180 FEET

1" = 60'

PROJECT LOCATION
2238 ROUTE 22
DOVER, NY 12594

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD
C	TOWN OF DOVER PLANNING BOARD SUBMITTAL	08-31-22	BRG	APG	BHR	BHR
B	TOWN OF DOVER PLANNING BOARD SUBMITTAL	04-26-22	BRG	APG	BHR	BHR
A	TOWN OF DOVER PLANNING BOARD SUBMITTAL	09-14-21	BRG	BHR	BHR	BHR

REFERENCE DRAWINGS

DSGN	BHR	08-26-21
DRN	BRG	08-26-21
CKD	BHR	08-12-22

SCALE: AS NOTED

FOR 24x36 DWG ONLY

POWER ENGINEERS

NY TRANSCO

DOVER STATION


LANDSCAPING PLAN

JOB NUMBER 169978

REV C

DRAWING NUMBER DVB-C1-120

DVB-C1-120.DWG



NORTH ELEVATION
(LKG SOUTH FROM ROUTE 26)

NOTE:

GRADES ARE BASED ON NAVD88 AND ARE MEASURED IN ACCORDANCE TOWN OF DOVER CODE CHAPTER 145 - ZONING

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD	REFERENCE DRAWINGS
C	Town of Dover Planning Board Submittal	31 AUG 2022	AH	AH	JM	JM	
B	Town of Dover Planning Board Submittal	26 APR 2022	AH	AH	RC	RC	
A	Town of Dover Planning Board Submittal	14 SEP 2021	AH	AH	JC	JC	

DSGN	AH	06/10/21
DRN	AH	06/10/21
CKD	JC	06/11/21

SCALE: 1"=30'-0"
FOR 24x36 DWG ONLY


POWER ENGINEERS

Dover Station
A New York Transco Project

NYTransco
Dover Station
Dover, NY

NORTH ELEVATION

JOB NUMBER 169978
REV C
DRAWING NUMBER DVB-E2-110



WEST ELEVATION

(LKG. EAST FROM ROUTE 22)

NOTE:

GRADES ARE BASED ON NAVD88 AND ARE MEASURED IN ACCORDANCE TOWN OF DOVER CODE CHAPTER 145 - ZONING

Dover Station
A New York Transco Project

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD	REFERENCE DRAWINGS
C	Town of Dover Planning Board Submittal	31 AUG 2022	AH	AH	JM	JM	
B	Town of Dover Planning Board Submittal	26 APR 2022	AH	AH	RC	RC	
A	Town of Dover Planning Board Submittal	14 SEP 2021	AH	AH	JC	JC	

DSGN	AH	06/10/21
DRN	AH	06/10/21
CKD	JC	06/11/21

SCALE: 1"=20'-0"

FOR 24x36 DWG ONLY

POWER ENGINEERS

NYTransco


Dover Station
Dover, NY

WEST ELEVATION

JOB NUMBER 169978

REV C

DRAWING NUMBER DVB-E2-111



PARTIAL PLAN VIEW

LEGEND:

- TASK LIGHT - ACUITY BRANDS HOLOPHANE TYPE PXLW, 30K
- AREA LIGHT - ACUITY BRANDS HOLOPHANE TYPE PMLED, 40K
- FLOOD LIGHT - LITHONIA LIGHTING TYPE DSXW1, 40K
- LIGHTNING MAST
- X.X SPOT LIGHT DENSITY (FOOT- CANDLE)
- LINE OF UNIFORM LIGHT DENSITY (FOOT- CANDLE)

NOTES:

1. AREA LIGHT AIMING POINT IS AT 45° FROM VERTICAL AND FIXTURE MOUNTING ELEVATION IS 20' ABOVE BOTTOM OF BASE PLATE (B.O.B.P.).
2. TASK LIGHT AIMING POINT IS AT DISCONNECT SWITCH BLADE AND FIXTURE MOUNTING ELEVATION IS 8'-6" ABOVE B.O.B.P.
3. CONTROL UNIT EXTERIOR FIXTURE MOUNTING ELEVATION IS 8'-6" ABOVE TOP OF CONCRETE.

Dover Station
A New York Transco Project

THIS DRAWING WAS PREPARED BY POWER ENGINEERS, INC. FOR A SPECIFIC PROJECT, TAKING INTO CONSIDERATION THE SPECIFIC AND UNIQUE REQUIREMENTS OF THE PROJECT. REUSE OF THIS DRAWING OR ANY INFORMATION CONTAINED IN THIS DRAWING FOR ANY PURPOSE IS PROHIBITED UNLESS WRITTEN PERMISSION FROM BOTH POWER AND POWER'S CLIENT IS GRANTED.

New York Transco

REV	REVISIONS	DATE	DRN	DSGN	CKD	APPD	REFERENCE DRAWINGS
C	Town of Dover Planning Board Submittal	31 AUG 2022	AH	AH	JM	JM	
B	Town of Dover Planning Board Submittal	26 APR 2022	AH	AH	RC	RC	
A	Town of Dover Planning Board Submittal	14 SEP 2021	AH	AH	JC	JC	

DSGN	AH	05/28/21
DRN	AH	05/28/21
CKD	JC	05/29/21

SCALE: 1"=30'-0"
FOR 24x36 DWG ONLY

POWER ENGINEERS

NYTranco
Dover Station
Dover, NY

LIGHTING PLAN

JOB NUMBER 169978
REV C
DRAWING NUMBER DVB-E7-101